



ELEVATION




SECTION AT-AA




PLAN SHOWING THE PROPOSED CONSTRUCTION OF RESIDENTIAL GROUND FLOOR BUILDING BELONGS TO SITUATED IN SY.NO:- 1036, LAY OUT NO. 340/87, PLOT NO. 12, BLOCK NO: 12, SRIMANNARAYANA COLONY, KODAD (MUNICIPALITY), NALGONDA (DT), TELANGANA. BELONGS TO - SRI THIPRISHETTI SATYANARAYANA S/O VEERAIAH


**RECEIVED**  
 Building permission accorded vide Proc.No. PCH/1011429/MA No. 302/2016. Dated: 17-2-2016. In the daily collecting an amount of Rs. 5670/- (Rupees Five Thousand Six Hundred and Seventy only) vide Receipt No. 024612183 Dated: 19-2-2016. This permission is valid upto: 16-2-2019.



GROUND FLOOR OPLAN & SITE PLAN



SITE PLAN SCALE 1:100



LOCATION MAP NOT TO SCALE

SPECIFICATION	
FOUNDATION	R.C.C.FOOTING IN 1:2:4 OVER C.C BED IN 1:5:10
BASEMENT	C.R.S MASONRY IN CM 1:0
SUPER STRUCTURE	BRICK MASONRY IN CM 1:6
ROOFING	R.C.C SLAB IN 1:2:4
PLASTERING	IN CM 1:4
FLOORING	MABLE STONES
WOOD WORK	CUNTRY WOOD

REFERENCE	
D DOOR	3'-6" X 7'-0"
W WINDOW	5'-0" X 5'-0"
V VENTILATOR	5'-0" X 1'-0"

AREAS	SFT		SQM
	SYD		
PLOT AREA	1049.40	116.60	97.47
ROAD EFFECTED AREA	90.00	10.00	8.36
NETT AREA	959.40	106.60	89.11
PLINTH AREA			
PROP: G.F	709.50	78.83	65.93
OPEN AREA	249.90	27.77	23.18
COMP.WALL	136.00 (R.F.T)		

PROPOSED SHOWN IN RED		
EXISTING SHOWN IN BLUE		
SET BACK	AS FOR G.O	AS FOR SITE
FRONT	1.50 M	1.50 M
REAR	0.00 M	0.00 M
SIDE- L	0.00 M	0.00 M
SIDE- R	0.00 M	1.06 M

OWNER'S SIGNATURE *T. Satyanarayana*

**VASTHU REKHA**  
 Architects Engineers & Builders  
 Main Road, KODAD-508 206

**VASTHU REKHA**  
 MAIN ROAD KODAD  
 ARCHITECTS, ENGINEERS & BUILDERS