



PLAN SHOWING THE PROPOSED CONSTRUCTION OF RESIDENTIAL GROUND FLOOR BUILDING SITUATED IN SY NO.1027/1, BLOCK NO-12, PLOT NO 25, KODADA (MUNICIPALITY) MARGONDA (DT), TELANGANA, BELONGS TO - SRI NALLAMOTHU RAJESHWARI W/O JAGADEESWAR RAO.




ELEVATION




SECTION AT-AA



ROUTE MAP PLAN



GROUND FLOOR PLAN & SITE PLAN



SITE PLAN SCALE 1:200

SPECIFICATION			
FOUNDATION	R.C.C FOOTING IN 1:2:4		
	OVER C.C BED IN 1:5:10		
BASEMENT	C.R.S MASONRY IN CM 1:8		
SUPER STRUCTURE	BRICK MASONRY IN CM 1:8		
ROOFING	R.C.C SLAB IN 1:2:4		
PLASTERING	IN CM 1:4		
FLOORING	MABLE STONES		
WOOD WORK	CUNTRY WOOD		

REFERENCE			
D	DOOR	3'-6" X 7'-0"	
W	WINDOW	5'-0" X 5'-0"	
V	VENTILATOR	5'-0" X 1'-0"	

AREAS	SFT	SYD	SQM
PLOT AREA	2730.00	303.33	253.71
ROAD EFFECTED AREA			
NET AREA	2730.00	303.33	253.71

PLINTH AREA	GF	1ST	2ND
GF	860.28	95.58	79.55
OPEN AREA	1869.72	207.74	173.76
COMP WALL	214.00 (R.F.T)		

PROPOSED SHOWN IN RED		
EXISTING SHOWN IN BLUE		
SET BACK	AS FOR G.O	AS FOR SITE
FRONT	2.00 M	8.68 M
REAR	1.00 M	1.00 M
SIDE - L	2.00 M	2.00 M
SIDE - R	1.00 M	1.00 M

OWNER'S SIGNATURE

Sanctioned
 Building permission accorded vide Proc. No. MCK/101/13 of 2015 dated 17-8-2015. Only collecting an amount of Rs. 3,535/- plus 1% penalty (if any) within 30 days from the date of sanction. Receipt No. 174782 dated: 31-8-2015 and this permission is valid upto 17-8-2018.

10/8/2015
 Commissioner
 Kodad Municipality

Ch. Nagaraj Rao
 Licensed Civil Engineer
 Lic. No. G14081/2014
VASTHU REKHA
 Architects Engineers & Builders
 Main Road, KODAD-508 205.